

Town of Rutland, Vermont

181 Business Route 4
Center Rutland, VT 05736



V. (802) 773-2528
F. (802) 773-7295

www.RutlandTown.com

The Town of Rutland is requesting pricing for multiple projects at our Municipal Town Hall.

Please provide us with your cost and time estimate for the projects below.

- 1) Replace existing main electrical distribution panel. The ideal scenario would be to eliminate the existing main and all sub-panels, consolidating them into 1 main panel. New panel should allow for additional circuits to be added in the future.

Total Estimated Cost - Time & Materials - \$ _____ Estimated time to complete: _____

- 2) Addition of 2 x 80w – 100w wall pack lights on the NE corners of the building and 2 x 80w – 100w wall pack lights on the West side of the building to be tied into existing timer circuit. Efficiency VT Lighting program preferred. Wall pack lights shall be installed as to not interfere with drivers on Business 4.

Total Estimated Cost – Lights - \$ _____ Time / Additional Materials - \$ _____

Estimated time to complete: _____

- 3) Install new LED light fixture over front door or retrofit existing fixture. Efficiency VT Lighting program preferred.

Total Estimated Cost – Lights - \$ _____ Time / Additional Materials - \$ _____

Estimated time to complete: _____

- 4) Replace light fixture over downstairs backdoor with appropriate flood light fixture.

Total Estimated Cost – Lights - \$ _____ Time / Additional Materials - \$ _____

Estimated time to complete: _____

- 5) Upgrade / add lighting for the back staircase, tied into existing switch. Efficiency VT Lighting program preferred.

Total Estimated Cost – Lights - \$ _____ Time / Additional Materials - \$ _____

Estimated time to complete: _____

- 6) Install new network cables in attic for POE compatible surveillance cameras. Cat 5 surface mount boxes to be installed inside the attic near where cables exit the building for each connection. Cables to be run along rafters/roof line to new surface mount boxes to be installed near where cables enter existing ceiling penetration to connect to DVR. Jumpers to be created to connect to DVR. All boxes / leads to be labeled at each connection point. Existing network cables and low voltage lines to be extended/replaced to allow running along rafters/roofline instead of across floor.

Total Estimated Cost - Time & Additional Materials - \$ _____ Estimated time to complete: _____

Our goal is to have all projects completed in a timely fashion. The Selectboard may elect to award individual projects based on time/cost estimates provided. Please indicate if you are willing to complete individual projects if they are awarded to your firm. Please include any additional information relevant to each project. Contact Bill Sweet at Town Hall at 802-773-2528 x 3203 with any questions on the project, or to schedule a time to look at the various project locations within our building. Projects must be completed, with invoices submitted on or before June 10th, 2022. Please mail or hand-deliver your quote by March 23rd, for review by the Selectboard at the March 29th meeting. The Town of Rutland Selectboard reserves the right to reject any or all bids/quotes in part or whole.